PLANTING NOTES			
1.	LANDSCAPE CONTRACTOR SHALL VISIT SITE PRIOR TO SUBMITTING BID TO BECOME COMPLETELY FAMILIAR WITH SITE CONDITIONS.		
2.	NO PLANTING WILL BE INSTALLED UNTIL ALL GRADING AND CONSTRUCTION HAS BEEN COMPLETED IN THE IMMEDIATE AREA.		
3.	CONTRACTOR TO VERIFY ALL UTILITIES ON PROPERTY AND TO PROTECT ALL UTILITIES DURING EXCAVATION.		
4.	IF THERE IS A DISCREPANCY BETWEEN THE NUMBER OF PLANTS SHOWN ON THE PLAN AND THE NUMBER OF PLANTS SHOWN IN THE PLANT LIST, THE NUMBER OF PLANTS SHOWN ON THE LIST WILL TAKE PRECEDENCE.		
5.	ALL CONTAINER MATERIAL TO BE GROWN IN CONTAINER A MINIMUM OF SIX MONTHS.		
6.	ALL MATERIAL SHALL COMPLY WITH THE LATEST EDITION OF THE AMERICAN STANDARD FOR NURSERY STOCK, ACCORDING TO THE AMERICAN ASSOCIATION OF NURSERYMEN.		
7.	CONTRACTOR SHALL REPAIR ALL DAMAGE TO PROPERTY FROM PLANTING OPERATIONS AT NO COST TO THE OWNER.		
8.	CONTRACTOR SHALL GUARANTEE NEW PLANT MATERIAL THROUGH ONE CALENDAR YEAR FROM TIME OF PROVISIONAL ACCEPTANCE.		
9.	ALL PROPOSED PLANTS SHALL BE LOCATED CAREFULLY AS SHOWN ON THE PLANS AND THE PLACEMENT SHALL BE APPROVED BY THE LANDSCAPE ARCHITECT BEFORE THE INSTALLATION.		
10.	ALL DISTURBED AREAS NOT TO BE PAVED OR PLANTED SHALL BE LOAMED AND SEEDED AS SHOWN. SEE SPECIFICATIONS FOR SOIL PREPARATION AND SEED MIX.		
11.	TWO INCH (2") DEEP, FINELY SHREDDED BARK MULCH WILL BE INSTALLED AROUND ALL TREES AND SHRUBS THAT ARE ISOLATED FROM GROUNDCOVER AREAS AND GENERAL SHRUB MASSES.		
12.	ALL PLANT MATERIAL SHALL BE INSPECTED BY THE LANDSCAPE ARCHITECT ON SITE PRIOR TO INSTALLATION. THE LANDSCAPE ARCHITECT WILL TAG ALL TREES AT THE NURSERY AND INSPECT THEM AFTER DELIVERY TO THE SITE. SEE SPECIFICATIONS FOR TAGGING, INSPECTION, AND ACCEPTANCE OF PLANT MATERIAL.		
13.	LANDSCAPE ARCHITECT SHALL CONFIRM PLANT LIST AND APPROVE SUBSTITUTIONS OF PLANT VARIETIES PRIOR TO ORDERING OF MATERIAL.		
14.	SOIL MIX: 1/3 PEAT MOSS, 1/3 SCREENED LOAM, 1/3 DEHYDRATED MANURE.		
PLANTING LEGEND			
	NATIVE PLANTINGS: DECIDUOUS SHRUBS 3 GAL. @ 4' OC MYRICA PENNSYLVANICA (BAYBERRY), CLETHRA ALNIFOLIA (SWEET PEPPERBUSH), VIBURNUM DENTATUM (ARROWWOOD VIBURNUM) NATIVE GROUNDCOVER AND GRASES: 1 GAL 4' O.C. VACCINIUM ANGUSTIFOLIUM (LOW BUSH BLUEBERRY), ARCTOSTAPHYLOS UVA-URSI (BEARBERRY), COMPTONIA PEREGRINA (SWEET FERN), PANICUM VIRGATUM (SWITCHGRASS)		
	GARDEN AREAS ORNAMENTAL SHRUBS (3-4' B&B, 4' OC) HYDRANGEA MACROPHYLLA, HYDRANGEA PANICULATA, CLETHRA ALNIFOLIA,	200' RI	
	BUDDLEIA DAVIDII, VITEX AGNUS CASTUS, CARYOPTERIS, ILEX GLABRA PERENNIALS & GROUNDOCVER (1 GAL, 2' OC)	ASSRPCL. 34-10 "N/F GARRY P. SAVAGE TRUST"	
	BAPTISIA, HEMEROCALLIS, GERANIUM, ECHINACEA PURPUREA, LAVANDULA, PEROVSKIA ATRIPLICIFOLIA, STACHYS BYZANTINA, NEPETA RACEMOSA, ALCHEMILLA MOLLIS, SEDUM 'AUTUMN JOY', PENNISETUM ALEPECUROIDES 'HAMLN'	<u>100'</u> CO <u>ASTA</u> L B <u>ANK SETBA</u>	
	LAWN: FESCUE BLEND SOD	100' WETL (100' SHORE 2	
	NATIVE MEADOW SCHYZACHIRIUM SCOPARIUM (LITTLE BLUESTEM), 20 LB/ACRE FESTUCA OVINA (SHEEP FESCUE), 5 LB/1,000 SF	<u>50' COAS</u> TAL BA <u>NK SETBA</u> C	
	LIMIT OF WORK		
	EXISTING STRUCTURE TO BE REMOVED	25' COASTAL BANK SETBAC	
		EXISTING BOARDWALK	
		EXISTING FLOATING PIER	
		TIASC	



HORIUCHI SOLIEN INC. P.O. BOX 914 200 MAIN STREET FALMOUTH MA 02541 508 540-5320 FAX 508 540-8651 info@horiuchisolien.com

HORIUCHI 😒 SOLIEN LANDSCAPE ARCHITECTS

> ARCHITECT HUTKER ARCHITECTS 79 BEACH ROAD PO BOX 2347 VINEYARD HAVEN, MA 02568 508-693-3344

**CIVIL ENGINEER** VINEYARD LAND SURVEYING & ENGINEERING, INC. I2 COURNOYER ROAD PO BOX 421 WEST TISBURY, MA 02575 508-693-3774

GENERAL CONTRACTOR STEDMAN CONSTRUCTION INC. PO BOX 1737 WEST TISBURY, MA 02575 401-252-1762

## SORRENTINO RESIDENCE

71 CARL'S WAY WEST TISBURY, MA

PROJECT NUMBER:	2290
DRAWN BY:	EH
CHECKED BY:	KMH
SCALE:	I"=30'-0"
DATE:	11.03.22
REVIEW:	11.03.22
DRAFT:	12.23.22
REVIEW:	12.29.22
CONCOMM-NOI:	01.27.23

LANDSCAPE PLAN