



Locus Map no scale

- Notes:
1. Silt fence backed by snow fence to be installed and maintained as shown throughout construction
 2. An on-site pre-construction meeting shall be held between the general contractor and a representative of the West Tisbury Conservation Commission
 3. Footprint of existing dwelling to be graded with random fill, dressed with 4" of topsoil and seeded
 4. Site grading to be random fill dressed with 4" of topsoil and seeded
 5. No stockpiling shall be allowed within the Buffer Zone
 6. Existing cesspool to be abandoned, pumped, and backfilled with clean sand.
 7. Existing well to be retained for irrigation use only
 8. Wetlands delineated by Cooper Environmental Services, Inc.
 9. Stone walls and edge of clearings taken from Col-East aerial survey



existing three-bedroom dwelling to be removed (historic portion to be relocated on site)



Site Plan
West Tisbury, Mass.

Prepared For
Christopher Cottrell

Scale: 1" = 50' Dec 19, 2018 (Jan 22, 2019 walls & env)

Schofield, Barbini & Hoehn Inc.
Land Surveying & Civil Engineering

12 Surveyor's Lane, Box 339
Vineyard Haven, Mass.
508-693-2781
www.sbhinc.net
MV 7129-Cottrell WTCC