







- 1. Existing well point to be pulled

- 2. Existing septic tank to be abandoned, pumped, crushed, and backfilled with clean sand
  3. Existing leaching trenches to be abandoned in place
  4. Wetlands delineated by Cooper Environmental Services, Inc. August 16, 2020
  5. Use of existing undefined parking area to be discontinued and restored per Landscape Plan
  6. Silt fence backed by construction fence or snow fence to be installed as shown prior to start of work
  - and shall be maintained as shown throughout construction
- ...denotes pine tree within Buffer Zone to be removed

Site Plan West Tisbury, Mass. **Prepared For** Duncley, LLC & Eversource

Scale: 1" = 40' August 19, 2020 (September 18, 2020)

Schofield, Barbini & Hoehn Inc. Land Surveying 

Civil Engineering

> 12 Surveyor's Lane, Box 339 Vineyard Haven, Mass. 02568 508-693-2781 www.sbhinc.net MV 1804 - Con Com

